BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate

Name of Work: Providing Basic facilities for Ganesha Immersion at Hebbal Lake Kalyani in Kodigehalli ward no. 8.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	150.00	Supply of Drinking Water through water tankers of Capacity 6000 Liters and Hiring of Water Tanker Hiring of Tractor 40HP including cost of warer and Engaging Heavy Mazdoor to deliver water including cost of fuel lubricants men and machinary etc. complete including	per Load	513.00	
2	12.00	Providing Stone dust to approach road and near immersion tank for levelling and to protect not to sliping Sl No. 50 Code 400 metal Component	cum	800.00	
3	90.00	Hire charge of pumping water 3.5 KL/hr capacity Pump	Hrs	50.00	
4	300.00	Providing Causal Labours (Unskilled mazdoor Heavy)	Days	258.88	
5	1590.00	Providing erecting removing casurinapole barricading using poles of 7.50 to 10 cms, dia and 1.5 height above ground fixed vertically at intervals of 2.0 to 2.5 mtrs. C/C an horizontally at 0.50 mtr, above ground level, including fixing poles in the ground level for minimum depth of 3.0 mtr and tied with coir rope firmly including cost and conveyance of all materials, labour, lead and lift charges and complete on hire basis as per the engineer in charge. (Approved Rate)	Mtrs	65.00	
6	54000.00	Hire Charge for Shamiyana with Necessary Bambo Poles, Erection Charges Including transportation - (Size: 60ft x 40ft = 2400 sqft) (Approved Rate)	Sft	8.00	
7	450.00	Hire Charges for Shamiyana Side Wall of 8ft Hight (Size: 10x 15ft = 150 Rft) (Approved Rate)	Rft	17.00	

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
8	720.00	Hire Charge for Armless Plastic Chairs (Approved Rate)	Nos	4.00	
9	300.00	Hire Charge for Wooden Table of Size 6ft x 2ft (Approved Rate)	Nos	40.00	
10	2250.00	Hire Charge for supplying and running circuit service main with necessary messanger wire and reel insulators and maintaining the same 4 of 25 sqmm PVC insulated and sheathedaluminium wire (KPWD SR 2010-11 P.55/I.6 III b)	Mtrs	9.00	
11	105.00	1321 Hire charge of 100 KVA Generator including operator, Fuel, transportation and Handling charges **(PWD SR 2016-17 (P.XXXXVII / I.92)**	Hrs	630.00	
12	420.00	Hire chargesfor Flood lighting arrangements for the stage and existing immersion Tank during night time (Approved Rate)	Nos	285.00	
13	10.00	1031 - Providing J.C.B Excavator on Hire basis including Operator and Fuel (P. XXXXVI/I. 23) PWD SR 2016-17	Day	670.00	

23/08

Byatarayanapura Division
BBMP, Bangalore - 92

23/08

Note:

1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)

2 Unit rates and prices shall be quoted by the Tender in Indian rupees.

3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)

4 Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))